
RECLAMATION

Managing Water in the West








History of Hydrologic Loadings for A.R. Bowman Dam

- Deterministic
 - Probable Maximum Flood (PMF)
- Risk Based (Probabilistic)
 - Regional hydrologic data
 - Paleoflood data
 - Stochastic Flood Modeling

Deterministic -- PMF Components

- Rainfall: Computed PMP
 - HMRs
- Rainfall Runoff Model
 - Infiltration (loss) rates
 - Unit hydrograph
 - Lag times



A.R. Bowman Dam – 1984 PMF

PMF

- HMR 43 (72-hr storm)
- Peak 268,000 cfs
- Volume 1,034,000 ac-ft (15-day)
- Overtops by 21 feet

1992

- Modification Report submitted to OMB
- Reinforced Concrete Overtopping Protection

A.R. Bowman Dam – 1994 PMF

PMF

- HMR 57
- Peak 255,000 cfs
- Volume 770,000 ac-ft (15-day)
- Overtops by 18.6 feet

Road to Risk Based Evaluation

1997Mod Report withdrawn from OMB

- Ochoco Dam
- Repayment Issues
- Risk based analyses began

Risk Analysis

- Quantifying/qualifying the risks posed by a dam
 - How could failure occur?
 - How likely is it?
 - What would happen if it did?
 - What is known/unknown
- Considers consequences
- Ranking dams by risk
- Examines risk reduction

Failure Modes

Static loads

Seepage/piping, slope stability, foundation stability, operational problems

Floods

Overtopping, spillway failure, increased chance of static failure

Earthquakes

Foundation liquefaction, deformation, cracking, increased chance of static failure


Risk Identification

- Facility Reviews
 - Annual (Checkup)
 - Periodic (O&M focus)
 - Comprehensive (Complete workup)
- Performance Monitoring
 - Visual monitoring
 - Instrumentation readings
- Reports of Unusual Conditions

Risk

 P (failure) = P (load) x P (response)
 = Annual probability of structural failure

Risk = P (load) x P (response) x loss of life
 = Annual probability of loss of life



Results and Decision Making

- "A's" needs action immediately within 90 days
- "B's" cover a wide variety of actions that may be appropriate. Can be scheduled according to other priorities and funding availability. Risk reduction must be accomplished within 7 years.
- "C's" The need for actions to reduce risk or conduct studies diminishes. A reasonable and prudent category.

Examples of Risk Reduction Actions

- Short-term actions
 - Investigation of uncertainties
 - Reservoir restrictions
 - Increased monitoring
 - Operational changes
 - Upgraded EAP

Examples of Risk Reduction Actions

- Long-term actions
 - Load definition
 - Data collection
 - Structural modification
 - Long term reservoir restriction

Benefits of Risk Assessment

- Assess condition of Reclamation structures over a full range of loading conditions
- Improved consistency in decisions
- Better focus in SOD recommendations
- Better evaluation of proposed modifications and their associated risk reduction
- Better definition of objectives in scoping out work products


Benefits (con't)

- Complies with Federal Guidelines for Dam Safety
- More complete thought processes. Assess condition of Reclamation structures over a full range of loading conditions (extreme and lesser conditions)
- Aid in making decisions to protect public from consequences of dam failure
- Assist in prioritizing the allocation of resources
- Support justifications for risk reduction action
- Credibility in USBR and OMB
- Allows for more modifications to be done with the limited resources (money) allocated


A.R. Bowman Hydrologic Risk Evaluation

- Two Flood Hazard Approaches
 - Paleoflood Study
 - Stochastic Modeling
- Both Approaches Indicate the Magnitude of the 1/10,000 flood < 25 % of the PMF
- Needed an order of magnitude greater protection due to the magnitude of downstream impacts

Paleostage Indicators











Figure A-1: Probability Curve from 2002 CFR Study (USBR 2002)





Comparison

	<u>Peak</u>	<u>Volume</u>
PMF (1994)	255,000 cfs	770,000 ac-ft
1,000 year	24,800 cfs	216,100 ac-ft
10,000 year	37,700 cfs	329,400 ac-ft

Total discharge < 12,000 cfs @ max water surface

Decision Making

- Other Major Factors In Final Decisions
- Legal
- Overall Technical Case
- Political
 - Operational
 - Public Involvement
- Environmental
- International

High Risk Dams

- Use redundant measures
- Design for very low probability loading conditions
- Use best available technology
- Strive for lowest level of risk that can reasonably be achievable
- Consider how we would construct the dam today



Karen Weghorst, PE Program Manager, Dam Safety Office



Arial Bold – 36 Point


- First Level 24 Point, Arial Bold
 - Second level 20 Point, Arial Bold
 - Third level 18 Point, Arial Bold
 - Fourth level 16 Point, Arial Bold
 - » Fifth level 14 Point, Arial Bold
- All Left Justified, No Centering

Stochastic Modeling Elements

- Hydrometeorological Parameters Treated as Variables
- Utilized 3-Day Storms and 15-Day Sequence of Storms
- Runoff Computed using Distributed Approach
- Perform 2500 Simulations to Examine Combinations
 Conducive to Large Floods

Probabilistic Events

- Flood Frequency Analysis
 - Gage data
 - Log Pearson Type III frequency analysis
 - Bulletin 17B.
- Paleoflood Analysis
 - Past or ancient flood event which occurred prior to the time of human observation or direct measurement by modern hydrological procedures.



Stochastic Simulation Flow Chart

Evaluation of risk results

- Decisions documented by decision makers
- Decisions need to be prioritized according to limited resources (time, funding, staffing)
- Decisions based on risk estimates and factors influencing these estimates
- Decisions based in incomplete/imperfect data need to determine benefit gained by obtaining more data
- Risk reduction actions should reduce overall risks as low as can reasonably be achieved
- Credible evidence of developing failure mode